



## KAÉDI / M'BOUT / SELIBABY / GOURAYE ROAD (305 KM)

DETAILED DESIGN; TECHNICAL ASSISTANCE DURING CONSTRUCTION.



**Client:** Islamic Republic of Mauritania / Norvia, S.A.

**Location:** Islamic Republic of Mauritania

**Design date:** 2007 - 2008

**Construction date:** 2008 - 2009

**Services:** Detailed Design; Technical assistance during construction.

**Construction:** Construtora do Tâmega, SA / AFA – Avelino Farinha & Agrela

**Summary:**

16 bridges with a 16.8 m long standard span built with precast reinforced concrete beams in an area with shortage of water and without conditions for concrete transportation. 223 reinforced concrete multi-cell culverts (1 to 24 cells), with both precast and cast on site components.

[SEE ONLINE](#)